INTERIOR WALL TYPES

WALL TYPE		FIRE RATING & TEST NO.	STC RATING & TEST NO.	GRAPHIC	DESCRIPTION	REMARKS
IW1b	INTERIOR WALL CONSTRUCTION	N / A	N / A	0.66 m	- 13mm G.W.B. - 64mm STEEL STUDS @ 400mm O.C. - 13mm G.W.B.	
IW1c	INTERIOR WALL CONSTRUCTION	N / A	N / A	0.172 m	- 13mm G.W.B. - 92mm STEEL STUDS @ 400mm O.C. - 13mm G.W.B.	
IW1d	INTERIOR WALL CONSTRUCTION	N / A	N / A	0.18 m	- 13mm G.W.B. - 152mm STEEL STUDS @ 400mm O.C. - 13mm G.W.B.	
IW1f	INTERIOR WALL CONSTRUCTION - FINISHED ONE SIDE	N / A	N / A	0.66 m	- 13mm G.W.B. - 64mm STEEL STUDS @ 400mm O.C.	
IW1i	INTERIOR WALL CONSTRUCTION - FINISHED ONE SIDE	N / A	N / A	0.172 m	- 13mm G.W.B. - 92mm STEEL STUDS @ 400mm O.C.	
IW1f	G.W.B. ON FURRING CHANNEL WALL CONSTRUCTION	N / A	N / A	0.64 m	- 13mm G.W.B. - 22mm STEEL FURRING CHANNELS - CAST-IN-PLACE CONCRETE WALL OR CONCRETE BLOCK WALL	NOTE: REFER TO PLANS FOR SUBSTRATE WALL.
IW1s	G.W.B. LAMINATE ON CONCRETE WALL CONSTRUCTION	N / A	N / A	0.13 m	- 13mm G.W.B. - CAST-IN-PLACE CONCRETE WALL SUBSTRATE	NOTE: REFER TO PLANS FOR SUBSTRATE WALL. G.W.B TO BE LAMINATED DIRECTLY TO SUBSTRATE WALL USING GROOVED, TROWEL APPLIED ADHESIVE.
IW2b	INTERIOR WALL CONSTRUCTION	N / A	N / A	0.66 m	- 13mm G.W.B. - 64mm STEEL STUDS @ 400mm O.C. - 64mm ACOUSTIC BATT INSULATION - 13mm G.W.B.	
IW2c	INTERIOR WALL CONSTRUCTION	N / A	N / A	0.172 m	- 13mm G.W.B. - 92mm STEEL STUDS @ 400mm O.C. - 89mm ACOUSTIC BATT INSULATION - 13mm G.W.B.	
IW2f	INTERIOR WALL CONSTRUCTION - FINISHED ONE SIDE	N / A	N / A	0.66 m	- 13mm G.W.B. - 64mm STEEL STUDS @ 400mm O.C. - 64mm ACOUSTIC BATT INSULATION	
IW2g	INTERIOR WALL CONSTRUCTION - FINISHED ONE SIDE	N / A	N / A	0.1 m	- 13mm G.W.B. - 92mm STEEL STUDS @ 400mm O.C. - 89mm ACOUSTIC BATT INSULATION	
IW2l	GARBAGE CHUTE / ELEVATOR / MECHANICAL SHAFT TO SUITE	N / A	STC 55 Based on NRC Test TL-88-474 (140mm concrete block) & NRC Test TL-88-393 (190mm concrete block)	0.1 m	- CAST-IN-PLACE CONCRETE WALL OR CONCRETE BLOCK WALL (REFER TO PLANS FOR WALL TYPE) - 25mm AIR SPACE - 64mm STEEL STUDS @ 600mm O.C. ON CONT. NEOPRENE STRIP BELOW RUNNER - 64mm ACOUSTIC BATT INSULATION - 16mm G.W.B.	NOTE: G.W.B. TO BE SEALED WITH ACOUSTICAL SEALANT (ALL SIDES). REFER TO GARBAGE CHUTE DETAILS ON TYPICAL DETAILS SHEET.
IW2m	THERMALLY INSULATED STUD FURRING WALL	N / A	N / A	0.08 m	- 64mm STEEL STUDS @ 600mm O.C. ON CONT. NEOPRENE STRIP BELOW RUNNER - 64mm ACOUSTIC BATT INSULATION (RSI 1.41/R8) - SMART VAPOUR BARRIER, SEALED ALL SIDES - 13mm G.W.B.	NOTE: REFER TO PLANS FOR SUBSTRATE WALL.
IW3a	FIRE RATED WALL	1HR	ULC No. W453	N / A	0.2 m	- 16mm FIRE-RATED G.W.B - 92mm STEEL STUDS @ 400mm O.C. - 89mm ACOUSTIC BATT INSULATION - 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW3c	FIRE RATED WALL	2HR	ULC No. W453	STC 55 OBC SB-3 S6b	0.18 m	- 2 LAYERS 16mm FIRE-RATED G.W.B. - 92mm STEEL STUDS @ 400mm O.C. - 89mm ACOUSTIC BATT INSULATION - 2 LAYERS 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW3c	FIRE RATED WALL	1HR	ULC No. W453	N / A	0.18 m	- 16mm FIRE-RATED G.W.B. - 152mm STEEL STUDS @ 400mm O.C. - 152mm ACOUSTIC BATT INSULATION - 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW3d	FIRE RATED WALL	2HR	ULC No. W453	N / A	0.22 m	- 2 LAYERS 16mm FIRE-RATED G.W.B. - 152mm STEEL STUDS @ 400mm O.C. - 152mm ACOUSTIC BATT INSULATION - 2 LAYERS 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW3e	SUITE TO CORRIDOR WALL	1HR	ULC No. W453	STC 54 Based on NRC-CNRC Report IRC-IR-761 Tests TL-92-368	0.14 m CORRIDOR SUITE	- 2 LAYERS 16mm FIRE-RATED G.W.B. - 92mm STEEL STUDS @ 600mm O.C. - 89mm ACOUSTIC BATT INSULATION - 16mm FIRE-RATED G.W.B.	NOTE: G.W.B. TO BE SEALED (ALL SIDES). WALL TO BE INSTALLED AS PER ULC LISTING. STUD SPACING TO BE 400mm O.C. WHERE WALL HEIGHT EXCEEDS 3050mm (NRC-CNRC Report IRC-IF-761 Test TL-92-420).
IW3f	SUITE TO CORRIDOR WALL	2HR	ULC No. W453	STC 58 Based on NRC-CNRC Report IRC-IR-761 Tests TL-92-369	0.18 m	- 2 LAYERS 16mm FIRE-RATED G.W.B. - 92mm STEEL STUDS @ 600mm O.C. - 89mm ACOUSTIC BATT INSULATION - 2 LAYERS 16mm FIRE-RATED G.W.B.	NOTE: G.W.B. TO BE SEALED (ALL SIDES). WALL TO BE INSTALLED AS PER ULC LISTING. STUD SPACING TO BE 400mm O.C. WHERE WALL HEIGHT EXCEEDS 3050mm (NRC-CNRC Report IRC-IF-761 Test TL-93-331).
IW3g	SUITE TO SUITE DEMISING WALL	1HR	ULC No. W453 * FIRE RATING FOR THIS ASSEMBLY	STC 50 Based on NRC-CNRC Report IRC-IR-761 Tests TL-92-368	0.23 m SUITE SUITE	- 2 LAYERS 16mm FIRE-RATED G.W.B.* - 92mm STEEL STUDS @ 600mm O.C.* - 89mm ACOUSTIC INSULATION* - 16mm FIRE-RATED G.W.B.* - 12mm AIR SPACE - 64mm STEEL STUDS @ 400mm O.C. - 64mm ACOUSTIC BATT INSULATION - 13mm G.W.B.	NOTE: G.W.B. TO BE SEALED (ALL SIDES). WALL TO BE INSTALLED AS PER ULC LISTING. STUD SPACING TO BE 400mm O.C. WHERE WALL HEIGHT EXCEEDS 3050mm (NRC-CNRC Report IRC-IR-761 Test TL-92-420). ALIGN G.W.B. FINISH SIDE(S) WITH SHEAR WALL IF REQUIRED.
IW4a	SHAFT WALL	1HR	ULC No. W452 System B	N / A	0.08 m SHAFT SIDE	- 25mm SHAFT WALL LINER PANEL - 64mm STEEL C-H STUDS @ 600mm O.C. - 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW4b	SHAFT WALL	2HR	ULC No. W452 System B	N / A	0.1 m SHAFT SIDE	- 25mm SHAFT WALL LINER PANEL - 64mm STEEL C-H STUDS @ 600mm O.C. - 2 LAYERS 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW4c	SHAFT WALL	2HR	ULC No. W452 System B	N / A	0.13 m SHAFT SIDE	- 25mm SHAFT WALL LINER PANEL - 102mm STEEL C-H STUDS @ 600mm O.C. - 2 LAYERS 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW4d	SHAFT WALL	2HR	ULC No. W452 System B	N / A	0.18 m SHAFT SIDE	- 25mm SHAFT WALL LINER PANEL - 152mm STEEL C-H STUDS @ 600mm O.C. - 2 LAYERS 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW4e	SHAFT WALL	2HR	ULC No. W452 System B	STC 50 RAL-OT-04-019	0.13 m SHAFT SIDE	- 25mm SHAFT WALL LINER PANEL - 102mm STEEL C-H STUDS @ 600mm O.C. - 75mm ACOUSTIC BATT INSULATION - 2 LAYERS 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW4f	SHAFT WALL	2HR	ULC No. W452 System G	STC 56 NRC TL-94-038	0.13 m SHAFT SIDE	- 25mm SHAFT WALL LINER PANEL - 102mm STEEL C-H STUDS @ 600mm O.C. - 75mm ACOUSTIC BATT INSULATION - 3 LAYERS 16mm FIRE-RATED G.W.B.	NOTE: WALL TO BE INSTALLED AS PER ULC LISTING. PROVIDE ACOUSTICAL SEALANT AROUND PERIMETER.
IW6a	INTERIOR WALL CONSTRUCTION - CONCRETE BLOCK	1HR	CCMPA	STC 46 CCMPA	0.14 m	- 140mm HOLLOW CONCRETE BLOCK (58% SOLID)	NOTE: REFER TO FIRE SEPARATION DIAGRAMS FOR FIRE RESISTANCE RATING. STC RATINGS BASED ON 'TYPE A' CONCRETE BLOCK.
IW6b	INTERIOR WALL CONSTRUCTION - CONCRETE BLOCK	2HR	CCMPA	STC 47 CCMPA	0.14 m	- 140mm 75% SOLID CONCRETE BLOCK (78% SOLID)	NOTE: REFER TO FIRE SEPARATION DIAGRAMS FOR FIRE RESISTANCE RATING. STC RATINGS BASED ON 'TYPE A' CONCRETE BLOCK.
IW6c	INTERIOR WALL CONSTRUCTION - CONCRETE BLOCK	1HR	CCMPA	STC 50 CCMPA	0.19 m	- 190mm HOLLOW CONCRETE BLOCK (56% SOLID)	NOTE: REFER TO FIRE SEPARATION DIAGRAMS FOR FIRE RESISTANCE RATING. STC RATINGS BASED ON 'TYPE A' CONCRETE BLOCK.
IW6d	INTERIOR WALL CONSTRUCTION - CONCRETE BLOCK	2HR	CCMPA	STC 53 CCMPA	0.19 m	- 190mm 75% SOLID CONCRETE BLOCK (78% SOLID)	NOTE: REFER TO FIRE SEPARATION DIAGRAMS FOR FIRE RESISTANCE RATING. STC RATINGS BASED ON 'TYPE A' CONCRETE BLOCK.
IW9a	CAST-IN-PLACE CONCRETE WALL	2HR	OBC SB-2 TABLE 2.1.1.	STC 50 STC 56 (MIN. 200mm)	0.20 m	- CAST-IN-PLACE CONCRETE WALL AS INDICATED (REFER TO STRUCTURAL DWGS.)	NOTE: CAST-IN-PLACE CONCRETE TO B/E 130mm (TYPE S) OR 120mm (TYPE N) FOR FIRE RATING REQUIREMENT. REFER TO FIRE SEPARATION DIAGRAMS FOR FIRE RESISTANCE RATING.

FLOOR TYPES

FLOOR TYPE		FIRE RATING & TEST NO.	STC RATING & TEST NO.	GRAPHIC	DESCRIPTION	REMARKS
F1a	CONCRETE FLOOR SLAB	N / A	N / A	0.20 m	- CAST-IN-PLACE CONCRETE SLAB (REFER TO STRUCTURAL DWGS.)	NOTE: UNDERSLAB FINISH ROLL ON STUCCO FINISH AT EXTERIOR EXPOSED CONCRETE (TYPICAL)
F1c	CONCRETE FLOOR SLAB-ON-GRADE	N / A	N / A	VARIES	- CONCRETE SEALER (REFER TO ROOM FINISH SCHEDULE) - CAST-IN-PLACE CONCRETE SLAB SLOPED FOR DRAINAGE (REFER TO STRUCTURAL DWGS.) - 15mil POLY VAPOUR BARRIER (AS NOTED ON SLAB EDGE DWGS.) - UNDERSLAB DRAINAGE SYSTEM (REFER TO MECHANICAL DWGS.) - COMPACTED FILL OR UNDISTRIBUTED NATIVE SOIL (REFER TO GEOTECHNICAL REPORT)	NOTE: MIN. 2% SLOPE TO DRAIN. REFER TO GEOTECHNICAL REPORT. VAPOUR BARRIER REQUIRED UNDER AREAS TO RECEIVE FLOOR FINISH. TF NOTE: VERIFY ASSEMBLY WITH GEOTECHNICAL REPORT. INDICATE LOCATION OF VAPOUR BARRIER BELOW TILE FINISH ON SLAB EDGE DWG. IF REQUIRED
F1f	LOADING BAY FLOOR SLAB	N / A	N / A	0.15 m	- 150mm CAST-IN-PLACE CONCRETE SLAB (REFER TO STRUCTURAL DWGS.) - HEAVY DUTY DRAINAGE BOARD - RUBBERIZED ASPHALT MEMBRANE WATERPROOFING WITH SEPARATION SHEET - CAST-IN-PLACE CONCRETE SLAB SLOPED TO DRAIN (REFER TO STRUCTURAL DWGS.)	NOTE: MIN. 2% SLOPE TO DRAIN. FOR FLOOR FINISH, REFER TO ROOM FINISH SCHEDULE.
F2a	FLOATING FLOOR	N / A	N / A	0.15 m	- 100mm CAST-IN-PLACE CONCRETE SLAB (REFER TO STRUCTURAL DWGS.) - 13mm PLYWOOD - VIBRATION ISOLATION PADS - 50mm SEMI-RIGID MINERAL WOOL INSULATION - CAST-IN-PLACE CONCRETE SLAB (REFER TO STRUCTURAL DWGS.)	NOTE: REFER TO ACOUSTIC REPORT AND MANUFACTURER'S DETAILS. AT FLOATING CONCRETE FLOOR, PROVIDE PERIMETER ISOLATION BOARDS AND ACOUSTICAL SEALANT. FOR FLOOR FINISH, REFER TO ROOM FINISH SCHEDULE.
F2b	FLOATING FLOOR	N / A	N / A	0.15 m	- 100mm CAST-IN-PLACE CONCRETE SLAB (REFER TO STRUCTURAL DWGS.) - 13mm PLYWOOD - VIBRATION ISOLATION PADS - 50mm SEMI-RIGID MINERAL WOOL INSULATION - WATERPROOFING MEMBRANE - CAST-IN-PLACE CONCRETE SLAB (REFER TO STRUCTURAL DWGS.)	NOTE: REFER TO ACOUSTIC REPORT AND MANUFACTURER'S DETAILS. AT FLOATING CONCRETE FLOOR, PROVIDE PERIMETER ISOLATION BOARDS AND ACOUSTICAL SEALANT. FOR FLOOR FINISH, REFER TO ROOM FINISH SCHEDULE.
F2c	GARAGE RAMP (HEATED)	N / A	N / A	0.13 m	- 100mm CAST-IN-PLACE CONCRETE SLAB WITH HERRINGBONE PATTERN (REFER TO STRUCTURAL DWGS.) - HEATING CABLES (REFER TO ELECTRICAL DWGS.) OR HYDRONIC PIPING (REFER TO MECHANICAL DWGS.) - HEAVY DUTY DRAINAGE BOARD - 2-PLY RUBBERIZED ASPHALT MEMBRANE WATERPROOFING WITH SEPARATION SHEET - CAST-IN-PLACE CONCRETE SLAB SLOPED FOR DRAINAGE (REFER TO STRUCTURAL DWGS.)	
F2d	ACOUSTIC SUBFLOOR	N / A	N / A	0.08 m	- 75mm SOUND DAMPENING SUB-FLOOR - CAST-IN-PLACE CONCRETE SLAB (REFER TO STRUCTURAL DWGS.)	NOTE: REFER TO ACOUSTICAL REPORT AND MANUFACTURER'S DETAILS. FOR FLOOR FINISH, REFER TO ROOM FINISH SCHEDULE.

COM-Gym-SP-H/50 Floating Floor
- COM-GYMFLOAT50 isolators (50 mm thick, with batt insulation pads directly created by isolators);
- 19 mm plywood;
- COM-DAMP high damping layer (5 mm);
- 19 mm plywood;
- COM-IMPACT shock absorbing underlayment (20 mm)
- rubber rollout floor (10 mm).

This floor has a total thickness of 123 mm.

Pliteq Gym Floating Floor
- Pliteq GenieMat FF70 Panelized Floating Floor (70 mm thick, including isolators, batt insulation, and plywood);
- Additional 19 mm plywood layer; and
- GenieMat Fit30 fitness tile (30 mm thick).

This floor has a total thickness of 119 mm.

EXTERIOR WALL TYPES

WALL TYPE		FIRE RATING & TEST NO.	STC RATING & TEST NO.	GRAPHIC	DESCRIPTION	REMARKS
EW1a	STONE VENEER ON 152mm STRUCTURAL STEEL STUD BACKUP WALL	N / A	N / A	0.34 m	- 90mm STONE VENEER W/ STAINLESS STEEL BAYONETTE MASONRY ANCHORS W/ PLASTIC CLIP - 25mm AIR SPACE, VENT TOP & BOTTOM - 40mm RIGID INSULATION (RSI 1.32/R7.5) SECURED TO FACE OF SHEATHING WITH PLASTIC CLIP - SELF-ADHERED AIR BARRIER MEMBRANE (VAPOUR PERMEABLE) - 13mm EXTERIOR GRADE SHEATHING BOARD - 152mm STRUCTURAL STEEL STUDS @ 400mm O.C. -152mm SEMI-RIGID INSULATION (RSI 3.96/R22.5) - 6mil POLY VAPOUR BARRIER SEALED ALL SIDES - 13mm G.W.B.	NOTE: STEEL STUD CONTRACTOR TO SUBMIT SHOP DRAWINGS WITH P. ENG STAMP FOR APPROVAL.
EW1b	STONE VENEER ON CONCRETE WALL	N / A	N / A	0.16 m	- 90mm STONE VENEER W/ STAINLESS STEEL THERMAL BREAK MASONRY ANCHOR - 25mm AIR SPACE, VENT TOP & BOTTOM - 40mm RIGID INSULATION (RSI 1.32/R7.5) SECURED TO FACE OF CONCRETE WALL WITH PLASTIC CLIP - SELF-ADHERED AIR BARRIER MEMBRANE (VAPOUR PERMEABLE) - CAST-IN-PLACE CONCRETE WALL OR COLUMN (VAPOUR BARRIER) (REFER TO STRUCTURAL DWGS.)	TF NOTE: DESIGNER TO ADJUST MASONRY ANCHOR TYPE TO SUIT BUILDING HEIGHT (IF REQ'D). AVOID USING THIS WALL. GIVE PREFERENCE TO EW1c FULL OUTBOARD INSULATION
EW1c	STONE VENEER ON CONCRETE WALL (OUTBOARD INSUL.)	N / A	N / A	0.22 m	- 90mm STONE VENEER W/ STAINLESS STEEL THERMAL BREAK MASONRY ANCHORS - 25mm AIR SPACE, VENT TOP & BOTTOM - 100mm SEMI-RIGID INSULATION (RSI 2.96/R17) SECURED TO FACE OF CONCRETE WALL WITH PLASTIC CLIP - CAST-IN-PLACE CONCRETE WALL OR COLUMN (VAPOUR BARRIER) (REFER TO STRUCTURAL DWGS.)	
EW2a	SPANDREL GLASS PANEL IN WINDOW WALL SYSTEM	N / A	N / A	0.21 m	- SPANDREL PANEL IN 140mm ALUMINUM WINDOW-WALL FRAME SYSTEM - 75mm SEMI-RIGID MINERAL WOOL INSULATION (RSI 2.95/R17) IN GALVANISED METAL BACKPAN (AIR & VAPOUR BARRIER) - 41mm STEEL STUDS @ 400mm O.C. OFFSET 12mm FROM INTERIOR FACE OF W/ WINDOW WALL FRAME - 40mm THICK SEMI-RIGID INSULATION (RSI 1.47/R8) - 2mil SMART VAPOUR BARRIER - 13mm G.W.B. (AIR BARRIER), SEALED ALL SIDES	NOTE: REFER TO ELEVATIONS/WINDOW SCHEDULE FOR SPANDREL TYPE AND LOCATION.
EW2d	SPANDREL GLASS PANEL IN WINDOW WALL SYSTEM	N / A	N / A	0.23 m	- SPANDREL PANEL IN 140mm ALUMINUM WINDOW-WALL FRAME SYSTEM - 75mm SEMI-RIGID MINERAL WOOL INSULATION (RSI 2.95/R17) IN GALVANISED METAL BACKPAN (AIR & VAPOUR BARRIER) - 64mm STEEL STUDS @ 400mm O.C. OFFSET 8mm FROM INTERIOR FACE OF W/ WINDOW WALL FRAME - 40mm THICK SEMI-RIGID INSULATION (RSI 1.47/R8) - 2mil SMART VAPOUR BARRIER - 13mm G.W.B.	NOTE: REFER TO ELEVATIONS/WINDOW SCHEDULE FOR SPANDREL TYPE AND LOCATION.
EW6a	ACM PANEL ON STEEL STUD BACKUP WALL	N / A	N / A	0.08 m	- 50mm ALUMINUM PLATE WALL PANEL SYSTEM - 50mm SEMI-RIGID INSULATION (RSI 1.47/R8) - SELF-ADHERED AIR BARRIER MEMBRANE - 13mm EXTERIOR GRADE SHEATHING BOARD - 152mm STRUCTURAL STEEL STUDS @ 400mm O.C. -150mm SEMI-RIGID INSULATION (RSI 3.96/R22.5) - VAPOUR BARRIER SEALED ALL SIDES - 13mm G.W.B.	NOTE: STEEL STUD CONTRACTOR TO SUBMIT SHOP DRAWINGS WITH P. ENG STAMP FOR APPROVAL.
EW9a	INTERIOR INSULATED POURED CONCRETE WALL	N / A	OBC SB-2 TABLE 2.1.1.	0.11 m	- CAST-IN-PLACE CONCRETE WALL - 25mm RIGID INSULATION (RSI 0.88/R5) - 64mm STEEL STUDS @ 400mm O.C. - 89mm FIBREGLASS BATT INSULATION (RSI 2.11/R12) - SMART VAPOUR BARRIER, SEALED ALL SIDES - 13mm G.W.B. (AIR BARRIER)	

FOUNDATION WALL TYPES

WALL TYPE		FIRE RATING & TEST NO.	STC RATING & TEST NO.	GRAPHIC	DESCRIPTION	REMARKS
FW2a	POURED CONCRETE FOUNDATION WALL W/ DRAINAGE LAYER	N / A	N / A		- DRAINAGE BOARD (PREMANUFACTURED DRAINAGE SYSTEM) - CONTINUOUS WATERPROOFING MEMBRANE - CAST-IN-PLACE CONCRETE FOUNDATION WALL (REFER TO STRUCTURAL DWGS.)	NOTE: REFER TO GEOTECHNICAL REPORT FOR ADDITIONAL INFO AND COORDINATE WITH SPECIFICATIONS.

INTERIOR CEILING TYPES

CEILING TYPE		FIRE RATING & TEST NO.	STC RATING & TEST NO.	GRAPHIC	DESCRIPTION	REMARKS
CL1a	INTERIOR SUSPENDED CEILING	N / A	N / A	VARIES	- 13mm G.W.B. ON SUSPENDED OR FRAMED CEILING SYSTEM - STUCCO OR PAINT FINISH (REFER TO I.D. DWGS.)	NOTE: BATHROOM CEILING AND BULKHEADS WITH PIPE OFFSETS TO RECEIVE 150mm ACOUSTIC INSULATION.
CL3a	ACOUSTIC CEILING BELOW MECHANICAL PENTHOUSE	N / A	N / A	1.80 0.44 0.72 m 2.77 0.42 m 0.30 m	- AIR/MECHANICAL SPACE - 150mm ACOUSTIC INSULATION - 2 LAYERS OF 16mm G.W.B. ON SUSPENDED OR FRAMED CEILING SYSTEM C/W ISOLATION HANGERS - AIR/MECHANICAL SPACE - 13mm G.W.B. ON SUSPENDED OR FRAMED CEILING SYSTEM C/W ISOLATION HANGERS	NOTE: REFER TO ACOUSTICAL REPORT FOR ADDITIONAL INFORMATION.
CL3b	ACOUSTIC CEILING AT AMENITY	N / A	N / A	VARIES	- AIR/MECHANICAL SPACE - 150mm ACOUSTIC INSULATION - 2 LAYERS 16mm G.W.B. ON SUSPENDED OR FRAMED CEILING SYSTEM C/W ISOLATION HANGER - CEILING FINISH (REFER TO I.D. DRAWINGS)	NOTE: REFER TO ACOUSTICAL REPORT FOR ADDITIONAL INFORMATION.
CL3c	ACOUSTIC CEILING AT AMENITY	N / A	N / A	VARIES	- 100mm THICK FOIL-FACED SEMI-RIGID INSULATION MECHANICALLY FASTENED - AIR/MECHANICAL SPACE - 2 LAYERS OF 16mm G.W.B. ON SUSPENDED OR FRAMED CEILING SYSTEM C/W ISOLATION HANGERS - CEILING FINISH (REFER TO I.D. DRAWINGS)	NOTE: REFER TO ACOUSTICAL REPORT FOR ADDITIONAL INFORMATION.
CL3d	ACOUSTIC CEILING AT GARBAGE / LOADING ROOM	N / A	N / A	VARIES	- AIR/MECHANICAL SPACE - 150mm ACOUSTIC INSULATION - 3 LAYERS OF 16mm G.W.B. ON SUSPENDED OR FRAMED CEILING SYSTEM C/W ISOLATION HANGER - CEILING FINISH (REFER TO I.D. DRAWINGS)	NOTE: REFER TO ACOUSTICAL REPORT FOR ADDITIONAL INFORMATION.
CL3e	ACOUSTIC CEILING AT PARKING GARAGE	N / A	N / A	VARIES	- AIR/MECHANICAL SPACE - HEATING ELEMENTS WHERE REQUIRED (REFER TO MECH. & ELEC. DRAWINGS) - 150mm ACOUSTIC INSULATION - 13mm EXTERIOR GRADE G.W.B. ON SUSPENDED OR FRAMED CEILING SYSTEM C/W ISOLATION HANGERS - PAINT OR STUCCO FINISH	NOTE: REFER TO ACOUSTICAL REPORT FOR ADDITIONAL INFORMATION.
CL4a2H	BULKHEAD ENCLOSURE	2HR	BMEC No. 89-1-118	N / A	VARIES - HORIZONTAL MEMBRANE OR METAL DUCT ENCLOSURE - 25mm SHAFT WALL LINER PANEL - 64mm C-H STUDS SPANNING HORIZONTALLY @ 610mm O.C. - 3 LAYERS 13mm FIRE-RATED G.W.B. SEALED ALL SIDES - VERTICAL PART OF ENCLOSURE AS PER INTERIOR WALL TYPE IW4b	NOTE: RATING SUPPORTING TO BE INSTALLED IN SPAN OF CEILING EXCEEDS BMEC RULING OF 2130mm.

GENERAL NOTES

GENERAL NOTES
1. All formwork for holes in concrete walls to be filled with non-shrink grout.
2. Stud framing to be minimum 25 gauge unless otherwise noted.
3. Apply preventive pest control powder in all stud wall tracks, pipe spaces and other concealed spaces within stud partitions. Refer to Specifications.
4. Provide abuse resistant gypsum board in lieu of standard gypsum board @ the following rooms:
   - -Storage rooms
   - -Electrical rooms
   - -Mechanical rooms
   - -Garbage/recycling rooms
   - -Abuse resistant gypsum board to be same thickness and gypsum type (rated or non-rated) as shown on wall schedule
5. Guard rail design to meet requirements of OBC 4.1.5.15 and Supplementary Standard SB-13 "Glass in Guards"
6. Refer to structural drawings for all structural concrete floor slab thicknesses. Floor slabs to have minimum 2hr FRR per OBC Sb3 F1b.
7. Refer to ID drawings and room finish schedule for all floor finishes.

PARTITION NOTES

1. All suite mechanical spaces to be fully insulated with acoustic insulation or provide insulation wrap to all pipes within. Acoustic insulation scope of work to be by drywall contractor.
2. Metal studs and gypsum board must not directly contact any part of the fancoil casing, duct work or piping within suite partitions or ceilings.
3. Extend acoustic or rated gypsum board partitions full height to u/s of floor or roof slab above, unless otherwise indicated.
4. Seal perimeter joints and penetrations at all fire rated partitions with applicable ULC rated sealant systems. Refer to Specifications.
5. Refer to National Research Council Canada - IRC-IR-761 (Sound Transmission Through Gypsum Board Walls: Sound Transmission Results).
6. Provide gypsum board control joints in all sections of wall exceeding 6000mm in length. In fire rated walls, provide fire rated joints.
7. Use moisture resistant board around shower areas, bathtub enclosures.
8. All insulated interior walls, seal perimeter joints and penetrations with acoustic sealant.
9. Provide grab bar blocking (stud reinforcement) for all washrooms:
   - -At amenity and common areas
   - -At main bathrooms in all residential suites in compliance with OBC 3.3.4.8.
10. For all walls in amenity and common areas refer to I.D. drawings for finishes, special support requirements, and walls required double studs.
11. Substitute regular gypsum board with moisture resistant gypsum board in wet areas.
12. Steel studs shall be installed at intervals of not more than 400mm above suite entrance door openings or any door openings in fire separations as per OBC 9.24.2.4. (3) and (4) for non load bearing steel studs in fire separations as directed by OBC division B-3.1.7.1 (2) and SB-2 section 5.2.1.

EXTERIOR WALL NOTES

1. Where gypsum board is the air barrier, seal at top of slab, tape at underside of slab and at shear wall/column vertical terminations, window penetrations, etc.
2. When installing fan coil/heat pumps prior to exterior wall completion and where they are against an exterior wall, use 13mm thick exterior sheathing board in lieu of regular drywall behind the units. All terminations between the exterior sheathing board and regular drywall to be fully taped and sealed.
3. Weather Barrier (WB) (vapour permeable air barrier) to be fully bonded to substrate behind semi-rigid insulation, typical, for all rainscreen wall assemblies; masonry veneer, EIFS, pre-finished metal panels etc.
4. Exterior exposed concrete to have stucco finish on all exterior sides
5. Mineral Wool insulation between steel studs is to be friction fit in stud space. Provide support where required to prevent sagging.
6. Seal around all anchor penetrations through air barrier membranes to maintain integrity of air barrier.

CONCRETE BLOCK WALL NOTES

1. All concrete block partitions and walls to extend to u/s of floor or roof slab above, unless otherwise indicated.
2. Provide compressible joint filler continuous at top of all block walls and partitions. Seal joints where exposed.
3. Provide firestopping and smoke seals at perimeter joints and penetrations in fire rated partitions.
4. Provide lateral bracing at top of concrete block walls and partitions.
5. Refer to Structural drawings for details
6. Provide radius block at corners.
7. Fire ratings for the following materials are based on:
   - Concrete wall (Table 2.2.1.A. Supplementary Standards SB-2 to the OBC 2012)
   - 190/140 75% solid concrete block (Fire resistance rating of concrete block in hours, Canadian Concrete Masonry Producers' Association, CCMPA) - refer to Masonry Specification.
8. Refer to National Research Council Canada - IRC IR-566 update (Sound Transmission Loss Measurements Through 190mm and 140mm blocks with Added Drywall and Through Cavity Block Walls).

WINDOWS

1. EXTRACT FROM 2012 ONTARIO BUILDING CODE, 3.3.4.8. PROTECTION OF OPENABLE WINDOWS
   (1) EXCEPT AS PROVIDED BY SENTENCE (2), OPENABLE WINDOWS IN SUITES OF RESIDENTIAL OCCUPANCY SHALL BE PROTECTED BY
   (a) A GUARD WITH A MINIMUM HEIGHT OF 1070MM CONSTRUCTED IN ACCORDANCE WITH ARTICLE 3.3.1.17., OR
   (b) A MECHANISM CAPABLE OF CONTROLLING THE FREE SWINGING OR SLIDING OF THE OPENABLE PART OF THE WINDOW SO AS TO LIMIT ANY CLEAR UNOBSTRUCTED OPENING TO A SIZE THAT WILL PREVENT THE PASSAGE OF A SPHERE HAVING A DIAMETER MORE THAN 100MM
   (2) WINDOWS NEED NOT BE PROTECTED IN ACCORDANCE WITH SENTENCE (1) WHERE
   (a) THE ONLY OPENING HAVING GREATER DIMENSIONS THAN THOSE ALLOWED BY CLAUSE (1)(b) IS LOCATED HIGHER THAN 1070MM ABOVE THE FINISHED FLOOR, OR
   (b) THE BOTTOM EDGE OF THE OPENABLE PORTION OF THE WINDOW IS LOCATED LESS THAN 1800MM ABOVE THE FLOOR OR GROUND ON THE OTHER SIDE OF THE WINDOW.

NON-LOADBEARING MASONRY WALLS

1. Non-load bearing masonry walls are those that do not support floors or roofs, whether they are interior or exterior walls. Non-load bearing masonry is not part of the primary structural system.
2. Masonry work shall conform to all requirements and referenced standards as per the specifications.
3. The following table provided for non-load bearing masonry is for pricing only. These notes shall not be considered part of the construction documents. The successful masonry contractor shall assume full responsibility for the engineering design of non- load bearing masonry as per the drawings and shall coordinate design of the masonry with mechanical and electrical trades for wall openings.
4. Reinforcing of non-bearing masonry walls and maximum wall height limits to be the responsibility of the masonry contractor.

NON-LOAD BEARING MASONRY WALL (NON-SEISMIC ZONE)
15 MPa BLOCK, DEFLECTION L/150

WALL THICKNESS mm (inch)	INTERIOR (Non-Bearing Partition Wall)		
	Maximum Wall Height (mm) and Minimum Reinforcing		
	Pressure (kPa)		
	0.25	0.375	0.50
140 (6"